

# 95 EXPRESS PHASE 3 Broward & Palm Beach Counties







# 95 Express Phase 3 Industry Forum

**FDOT District 4** 



# INDUSTRY FORUM OUTLINE

- PUBLIC COMMENT
- OPENING REMARKS
- DBE SPECIALIZED DEVELOPMENT PROGRAM
- PROJECT BACKGROUND
- PROJECT LIMITS AND SEGMENTATION
- PROJECT SCOPE OF IMPROVEMENTS
- PROCUREMENT PROCESS AND SCHEDULE
- NEXT STEPS





# **PUBLIC COMMENT**







## **OPENING REMARKS**

Courtney Drummond, PE, Director of Transportation Operations

Gerry O'Reilly, PE, Director of Transportation Development







# DBE SPECIALIZED DEVELOPMENT PROGRAM








# PROJECT BACKGROUND







# REGIONAL EXPRESS LANES NETWORK









# 10-YEAR REGIONAL EXPRESS LANES NETWORK








# 95 EXPRESS WITHIN THE REGIONAL EL NETWORK

#### **Status and Schedule**

- Phase 1: SR 112 to GGI Opened to Traffic in 2008
- Phase 2: GGI to Broward Blvd.
   P&R Under Construction;
   Anticipated Completion in
   Spring 2015
- Phase 3: Stirling Rd. to Linton Blvd.; RFP(s) and Concept Design(s) Underway to Develop Segment 3A (S. of Broward Blvd. to Atlantic Blvd. With a Possible Extension to SW 10<sup>TH</sup> St.) for Design-Build Letting(s) in April 2015.





# 95 EXPRESS PHASE 3- NEPA HISTORY

3	PD&E Study	LDCA	Reevaluations
	North - Glades Rd. to Linton Blvd. (FM# 412420-1)	July 2010	Reevaluation approved for Managed Lanes in May 2013; Future Reevaluations to be scheduled
	Central - Oakland Park Blvd. to Glades Rd. (FM# 409359-1; 409355-1)	August 2013	Reevaluation ongoing, currently in consultation with FHWA
	South - Stirling Rd. to North of Oakland Park Blvd. (FM# 429804-1)	September 2013	Reevaluation ongoing, currently in consultation with FHWA






# PROJECT LIMITS AND SEGMENTATION







Griffin Rd

Stirling Rd

Sheridan St



1-95 Express Phase 2

Stirling Rd

Yamato Rd

tlantic Blvd

Palmetto Park Ro

**PLAN** 



# PROJECT SCOPE OF IMPROVEMENTS








# **ROADWAY**

#### **Typical Section - 3 GP Lanes**



- Convert Existing HOV Lanes to Tolled Express Lanes
- Adds One Additional Tolled Express Lane in Each Direction
- Existing General Purpose Lanes to Remain

#### Limits are:


- I-595 to Davie Blvd.
- Sample Rd. to Palmetto Park Rd.
- Glades Rd. to Congress Ave.





## ROADWAY

#### **Typical Section - 3 GP Lanes with Auxiliary Lanes**



- Convert Existing HOV Lanes to Tolled Express Lanes
- Adds One Additional Tolled Express Lane in Each Direction
- Existing Auxiliary Lanes to Remain
- Existing General Purpose Lanes to Remain

#### Limits are:


- Davie Blvd. to Broward Blvd.
- Commercial Blvd. to Sample Rd.
- Palmetto Park Rd. to Glades Rd.





#### ROADWAY

#### **Typical Section - 4 GP Lanes with Auxiliary Lanes**



- Convert Existing HOV Lanes to Tolled Express Lanes
- Adds One Additional Tolled Express Lane in Each Direction
- Existing Auxiliary Lanes to Remain (To be added Oakland Park Blvd. to Comm. Blvd.)
- Existing General Purpose Lanes to Remain

#### Limits are:


- Stirling Rd. to I-595
- Broward Blvd. to Commercial Blvd.
- Congress Ave. to Linton Blvd.






# **DESIGN EXCEPTIONS/VARIATIONS**

Design Element	Design Variation	Design Exception
Lane Width		X
Median Width	X	
Shoulder Width	X	X
Border Width	X	
Bridge Width		X
Vertical Clearance	X	X
Cross Slope	X	
Superelevation Transition	X	
Horizontal Alignment	X	
Vertical Alignment	X	
Horizontal Stopping Sight Distance	X	X
Horizontal Clearance	X	





# **INGRESS/EGRESS LOCATIONS**










### ITS

- Maintain and Upgrade Existing ITS Devices, Including Toll Amount and Lane Status DMS
- Two Proposed 144-Count Fiber
   Optic Backbone Cables on the NB
   Side of I-95
- DMS Subsystem
- CCTV Camera Subsystem
- MVDS Subsystem
- Power Distribution Subsystem
- System Integration and FTE Coordination










# **TOLLING**

- 16 Open Road Tolling (ORT) Points
  - NB, One 1-Lane ORT and Seven 2-Lane ORT
  - SB, One 1-Lane ORT and Seven 2-Lane ORT
- Non-Accessible Toll Gantries







# RAMP SIGNALING

- Operational Technique to Control the Rate of Traffic Entering an Expressway
- Improves the Flow of Traffic
   Entering the Mainline While
   Avoiding Lengthy Backups on the
   Entrance Ramps and Cross-Streets
- Used Successfully Along I-95 in Miami-Dade County Since 2010, With Marked Improvements and Benefits to Corridor Traffic Flow and Operating Speeds









# RAMP SIGNALING

#### Phase 3A

- Hallandale Beach Blvd.
- Pembroke Rd.
- Hollywood
   Blvd.
- Sheridan St.
- Stirling Rd.
- Griffin Rd.
- SR 84/Marina Mile Blvd.
- Davie Blvd.

- Broward Blvd.
- Sunrise Blvd.
- Oakland Park Blvd.
- Commercial Blvd.
- Cypress Creek Rd.
- Atlantic Blvd.
- Copans Rd.
- Sample Rd.
- SW 10th St.



\*Ramp Signals
Operational in Miami







# **LIGHTING**

- System Upgrades to Meet FDOT Lighting Standards
- Proposed Roadside
   Shoulder and Wall
   Mounted Light Poles
- Existing Median
   Barrier-Mounted Light
   Poles to Remain
- LED Lighting Retrofit for I-95 Corridor is Being Considered









# **STRUCTURES**

- 50 Mainline Bridge Widening's
- 11 New or Replacement Ramp or Cross-Street Bridges
- One Mainline I-95 Bridge Replacement
- Extensive Use of New Retaining Walls
- Pedestrian Bridge

Phase 3 Bridge Widening's		
Phase	Widening Area (SF)	
3A	158,000	
3B	31,000	
3C	340,000	
TOTAL	530,000 SF	











# **STRUCTURES**

- 135 Cantilever Sign Structures
- 11 Truss Span Sign Structures
- 71 Overhead ITS Structures
- 11 DMS Structures
- 12 Toll Gantry Structures









# PROPOSED SOUND BARRIER WALLS

~11,400 LinearFeet of GroundMounted



~19,100 Linear
 Feet of Shoulder
 Mounted









# **AESTHETIC REQUIREMENTS**

- Bridge Widening's Along I-95
  - Pier Column Shapes Shall Match the Shape of the Existing Bridge Columns
  - Substructure Type and Material Shall Remain Constant Over the Entire Length of the Widened Bridges.
- Sound Barriers
- Retaining Walls
  - Shall Match Existing Walls in Type and Color





## DRAINAGE

- StormwaterManagement Facilities
  - Linear Dry Detention and Retention Ponds (onsite swales)
  - Dry and Wet Detention Ponds (infield ponds)
  - Limited Exfiltration Trench (south of NFNR)
  - Avoid Landscape
     Opportunity Areas and
     Freshwater Forested
     Wetlands at Sunrise
     Blvd. Interchange
  - New/Modified Control Structures and Outfall Pipe Retrofits










# DRAINAGE

- Drainage Collection and Conveyance Systems
  - New Closed Drainage Systems Required Along Outsides in Barrier Wall and Guardrail/Shoulder Gutter Sections
  - Modifications to Closed Drainage Systems Required in Median to Accommodate PGP and Shoulder Width Changes
  - MSE Wall Drainage and Culvert Extensions Required, as well as Accommodation of Bridge Deck Runoff









# DRAINAGE

- Canal Dredging and Bank Stabilization
  - Bank Stabilization Currently Proposed in C-13 and C-14 Canals for Phase 3A
  - No Canal Dredging is Currently Proposed, but Subject to Change Per Ongoing SFWMD Right-of-Way Occupancy Permitting









- T&E Species
  - Endangered Species Biological Assessment Report (ESBA) and Wetland Evaluation Report (WER)
     Prepared During PD&E Study Phase
  - Consultations Conducted with FWS and NMFS for Wood Stork, Manatee, and Indigo Snake During PD&E Study
  - Consultations Re-initiated for Smalltooth Sawfish as Part of USACE Permit Process for Phase 3A














- Wetlands
  - Jurisdictional Wetland Survey, Environmental Assessments, and Wetland Impact and Mitigation Assessment Completed for Phase 3A; to be Refined for Phase 3B and 3C Pending Completion of Concept Plans









- Mitigation
  - Existing Credits from West Lake Park and Loxahatchee
     Mitigation Bank to be Used for Phase 3A and 3B Impacts
  - Phase 3C Impacts to be Mitigated With Future Credits Created Under Separate Pond Apple Slough Mitigation Projects
  - DB Firm Responsible for Costs of Any Additional Impacts and Mitigation









- Archaeological
  - Cultural Resources Assessment Survey (CRAS) Prepared During PD&E Study Phase
  - No Subsurface Construction Work Below Original Construction Limits at Woodlawn Cemetery (located on east side I-95, South of Sunrise Blvd.)
  - All Construction Within Vicinity of Woodlawn Cemetery Frontage to be Monitored







- Contamination
  - Department Prepared the Following:
    - Phase I CSER
    - Bridge ACM and LBP Surveys
  - Department
     Performing Level II
     Contamination
     Assessment for
     Phase 3A (Available with the Final RFP)









# **PERMITTING**

- Department Submitted Permit Applications in May 2014:
  - SFWMD Individual Conceptual ERP RAI #1 Received
  - SFWMD ROW Occupancy Permit(s) RAI #1 Pending
  - USACE Section 404 Dredge & Fill Permit RAI #1 Received
  - USACE Section 408 Approval(s) RAI #1 Pending
  - Permits complete anticipated prior to Price Proposal submittal date
  - SFWMD Water Use (Dewatering) Master Permit(s) in Place for FDOT District Four Projects
  - USCG Exemption (NFNR) and Advanced Approval (C-13) Obtained in October 2013












#### **PERMITTING**

- DB Firm Responsible for Obtaining Following Permits per Phase(s):
  - NPDES Construction Generic Permit(s)
  - SFWMD Standard General Construction ERP(s)
  - Modifications to SFWMD and USACE Permits due to Final Design and/or Construction Changes, Including Special Conditions Documentation in Support of SFWMD Master Dewatering Permit Requirements













#### **LANDSCAPE**

- Department to Provide the Following:
  - Tree Inventory for Phase 3 limits
  - Landscape Opportunity Plans Illustrating Areas to be Preserved for Future Landscape Opportunities and Locations Where Existing Trees Could Potentially be Relocated Within Project Limits
  - RFP Documentation on Types and Locations for Trees to be Relocated Outside of Project Limits
- DB Firm Responsible for:
  - Tree Relocation Plans and Landscape Opportunity Plan
  - Relocation of Suitable Native Trees Impacted by Construction:
    - Screening Sound Barriers and Industrial Areas
    - NE and NW Quadrants of I-95 at Oakland Park Blvd. and Cypress Creek Rd. Interchanges
    - Specified Locations Within the Adjacent Municipalities











#### **UTILITY COORDINATION**

- UAO Coordination Meetings:
  - Utility Kickoff Meeting on 05-02-2014
  - Utility Workshops on 05-19-2014 and 06-09-2014
  - 1-on-1 Individual
     Utility Coordination
     Meetings (multiple
     have been on-going)








#### UTILITY COORDINATION

- Department Prepared the Following Items for Phase 3A:
  - Utility Base Map
  - Preliminary Utility Conflict Matrix







#### UTILITY COORDINATION

- Department Coordinating with UAOs for Phase 3A:
  - Preliminary Utility Work Schedules
  - UAO Design Costs
  - Utility Relocation Costs
  - Subsurface Utility Engineering
- Streamlining Utility Coordination for DB Firms by Advancing UAO Utility Design Efforts for Unavoidable Utility Relocations
- DB Firm Responsible for All Costs Related to Utility Coordination and Utility Relocations









#### **GEOTECHNICAL**

- Department Prepared the Following:
  - Geotechnical Report (PD&E Study)
  - Additional Geotechnical Investigation Underway
    - Roadway
    - Drainage
    - Bridges
    - Retaining Walls
    - Sound Barriers
- DB Firm Responsible for all Other Geotechnical Investigations









#### **SURVEY**

- Department Prepared the Following:
  - Controlled Rasters (Aerials)
  - Alignment and Right-of-Way Survey
  - Aerial Planimetrics (Topo and DTM) for I-95 Mainline and Side-Streets
  - Supplemental Ground Topo and DTM Within Some Obstructed Areas (e.g. below bridges, and adjacent to sound barriers and landscape areas)
  - Bathymetric Survey and DTM Within Canal Crossings
  - Subsurface Utility Engineering
- DB Firm responsible for:
  - Full Design Survey
  - Existing Drainage Survey
  - Supplemental Topo and DTM in Obstructed Areas
  - Supplemental Subsurface Utility Engineering







#### **RIGHT-OF-WAY**

- Department Intent to Avoid/Minimize Construction Activities Outside the Existing Right-of-Way
  - Phase 3A Proposed Improvements are Entirely Within Existing Right-of-Way
  - Phase 3B Proposed Improvements are Within Existing Right-of-Way, with the Exception of a Partial Take Under Consideration at the SW 10<sup>th</sup> St. Interchange
  - Phase 3C Partial Takes Currently Being Evaluated Adjacent to I-595 Viaduct Between SFNR and SW 26th Terrace





#### **PUBLIC OUTREACH**

- Recent and Ongoing Outreach Efforts:
  - Elected Official Briefings
  - June 3, 2014 Public Workshop
- DB Firm Responsible for Ongoing Support to FDOT Public Information Officer for:
  - Community Awareness Program
  - Public Meetings/Workshops
  - Technical Assistance/Display Materials









# MAINTENANCE AND INCIDENT MANAGEMENT


#### **DB Firm Responsible for:**

- Routine Maintenance Activities, From Rightof-Way to Right-of-Way, for Project Length
- Long-Term
   Maintenance of Traffic
   (>30 mins.) Associated
   with Incidents
- Road Rangers Vehicles













- 14.5 Miles of Roadway Widening and Milling/ Resurfacing/Overbuild
- Broward Blvd. Bridge Railing Upgrades
- Broward Blvd. Exit Ramp Widening's
- 32 Mainline Bridge Widening's
- New Auxiliary Lanes
   Between Oakland Park
   Blvd. and Commercial
   Blvd.







#### PROPOSED SOUND BARRIER WALLS

Phase 3A Sound Barrier Walls					
Location Number	Type of Sound Barrier Wall	Approximate Length	Adjacent Community		
1	8' Tall Shoulder Mounted	1,966	River Gardens/ Sweeting Estates		
2	20' Tall Ground Mounted	1,320	River Gardens/ Sweeting Estates		
3	8' Tall Shoulder Mounted	4,072	Prospect Gardens and North Andrews Gardens		
4	8' Tall Shoulder Mounted	1,460	North Andrews Gardens		
5	8' Tall Shoulder Mounted	693	Laguna Daiota Apartes sucts		
	14' Tall Shoulder Mounted	1,121	Laguna Pointe Apartments		







#### PROPOSED SOUND BARRIER WALLS

Phase 3A Sound Ba	arrier Walls
-------------------	--------------

Location Number	Type of Sound Barrier Wall	Approximate Length	Adjacent Community
6	20' Tall Ground Mounted	1,740	Oaks of Pompano Apartments and Avondale Park
7	8' Tall Shoulder Mounted	1,000	Pine Tree Park
8	20' Tall Ground Mounted	1,180	Pine Tree Park
9	14' Tall Shoulder Mounted	1,966	Olive Glen Apartments
10	8' Tall Shoulder Mounted	1,242	Whispering Isles Apartments
11	16' Tall Ground Mounted	552	Parkway United Methodist Church

Shoulder Mounted: 13,500 LF Ground Mounted: 4,800 LF








- Potential Segmentation into Two Separate Projects:
  - 3A-1: South of Broward Blvd. to N. of Commercial Blvd.
  - 3A-2: N. of Commercial Blvd. to SW 10th St. (Base + Bid Alternative Limits)







1-95 Express Phase 2

Glades Rd

\*Oakland Park Blv


Boca del Mar




- 10.6 Miles of Roadway Widening and Milling/Resurfacing/Overbuild
- Hillsboro Canal Bridge Replacement and I-95 Reconstruction (raising 4'-5')
- Clint Moore Rd. Overpass Bridge Jacking/Lengthening or Replacement
- 11 Mainline Bridge Widening's




















- 4.8 Miles of I-95 Roadway Widening and Milling/Resurfacing/Overbuild
- SR 84 Interchange Reconstruction (replace EB and WB bridges and ramp bridges)
- Nine Mainline I-95 or I-595 Bridge Widening's (including Pond Apple Slough Viaduct)
- Two New Median to Median I-95/I-595
   Direct Connect Ramps and One I-595
   Braided Ramp




















## PROCUREMENT PROCESS AND SCHEDULE







- D-B Segments (Phases 3A, 3B, and 3C)
- Standard FDOT Two-Phase D-B Approach
- Phase I Expanded Letter of Interest
- Phase II Technical Proposal
  - Alternative Technical Concept (ATC) Meetings
  - Page Turn Meeting
  - Question & Answer Session
- Price Proposal
- Final Selection Formula (adjusted score)
  - Bid Price Proposal/Technical Score





- Phase I Expanded Letter of Interest
- 1. Design-Build Firm Name and Prequalifications
- 2. Past Performance Evaluations, Design-Build Project Experience, Organization, and Staffing: (0-7 Points)
- 3. Design-Build Project Requirements and Critical Issues: **(0-13 Points)**





- Phase I Expanded Letter of Interest
- 2. Past Performance Evaluations, Design-Build Project Experience, Organization, and Staffing: (0-7 Points)
  - Contractor and Consultant Grades
  - Similar Experience
  - Performance history with Other States
  - Environmental Record
  - Organization/Staffing/Coordination Plans





- Phase I Expanded Letter of Interest
- 3. Design-Build Project Requirements and Critical Issues: **(0-13 Points)** 
  - Understanding of DB Requirements
  - Identification of Critical Issues
  - Outline for Addressing Critical Issues





## KEY CONSIDERATIONS FOR D4 ELOI'S/TECHNICAL PROPOSALS

- Corridor Continuity and Functionality
  - Coordination and Compatibility Between Adjacent Projects
    - Geometrics
    - Signing
    - ITS
    - Lighting
    - Drainage
    - Maintenance of Traffic
- Project Commitments and Department Priorities
  - Expedited Construction of Sound Barrier Walls and Work on Cross-Streets, Broward Blvd. Ramps
  - Avoidance of Woodlawn Cemetery Impacts





# ENGINEERING DATA TO BE MADE AVAILABLE WITH FINAL RFP

- Electronic Survey Data
- Existing Utilities Base Map and Potential Conflict Matrix
- Concept Plans
- Typical Section Package
- Pavement Design Report
- Design Exceptions and Variations
- Right-of-Way Maps
- Master Signing, ITS and Lighting Plans
- Lighting Analysis Report
- Landscape Concept Design
- Geotechnical Reports

- SFWMD Individual (Conceptual) ERP
- SFWMD Standard Right of Way Occupancy Permit(s)
- SFWMD Water Use Permit (Master Dewatering)
- USACE Section 404 Dredge & Fill Permit
- Conceptual Drainage Report
- Bridge Hydraulics Report
- Cross Drain Report
- Sound Barrier and Retaining Wall Requirements and Locations





## CEI PROCUREMENT PROCESS

Phase 3A

Advertisement: 11/17/2014

• Shortlist: 1/5/2015

Final Selection: 2/9/2015





#### PHASE 3A PROCUREMENT SCHEDULE

Procurement Activity	3A-1	3A-2
Advertisement	August 11, 2014	September 29, 2014
Expanded Letters of Interest Due	August 29, 2014	October 17, 2014
Shortlist Posting	October 9, 2014	December 1, 2014
Final RFP Provided to D-B Firms	October 10, 2014	December 5, 2014
Technical Proposals Due	February 9, 2015	March 16, 2015
Price Proposals Due	April 1, 2015	May 11, 2015
Anticipated Award Date	April 16, 2015	June 8, 2015
Anticipated Execution Date	May 7, 2015	June 22, 2015







#### **NEXT STEPS**







#### **NEXT STEPS**

- One-on-One Meetings July 30-31,
   2014 @ D4 Headquarters
  - D4 Management Team Discuss D4 and DB Firm Questions/Issues
  - Technical Review Committee (TRC)
- Phase 3A Draft RFP Posted on FDOT D-B Website
- 3A-1 DB Advertisement: 8/11/2014
- 3A-2 DB Advertisement: 9/29/2014





#### **PROJECT CONTACTS**

Before Advertisement:

Robert Bostian, Jr., PE

**Project Manager** 

Office: (954) 777-4427

E-mail: Robert.Bostian@dot.state.fl.us

Jim Hughes, PE

**Project Manager** 

Office: (954) 777-4419

E-mail: James. Hughes@dot.state.fl.us

After Advertisement:

**Esther Brandt** 

**Procurement Officer** 

Office: (954) 777-4620

E-mail: Esther.Brandt@dot.state.fl.us








#### PROJECT WEBSITE

Go to Website for Updates on Segmentation,
 Concepts, Presentations, Reports, etc.

www.95express.com/phase3







## QUESTIONS





